

# 加速勾配の現状と見通し

高エネルギー加速器研究機構  
加速器研究施設 加速器第6研究系

加古 永治


◆ 海外での高加速電界性能の現状

◆ 国内での高加速電界性能の現状

◆ 超伝導高周波試験施設での今後の展開

◆ 国内企業などでの空洞開発状況

◆ 今後の展望とまとめ






# 高加速電界性能の現状のまとめ

by C. Ginsburg (FNAL)

38 cavities  
2<sup>nd</sup> Pass


Electropolished 9-cell cavities  
JLab/DESY/KEK (combined) up-to-second successful test of  
cavities from established vendors




11 Large Grain Cavities:  
Eacc,max < 30 MV/m, after CP



$Q_0(E_{acc})$  of the LG cavities AC112- AC114, AC151-AC158 at 2K after BCP.



$Q_0(E_{acc})$  performance of the LG cavities AC112- AC114, AC151-AC158 at 2K after 50-120  $\mu\text{m}$  EP, 800° C, baking.



AC151, AC152 and AC 157 are in retreatment at DESY (add. EP)

m rough BCP, annealing at 800° C for 2h, final BCP of 20  $\mu\text{m}$  and C for 48h. AC112 is not baked; AC113and AC114 are baked after additional 20 $\mu\text{m}$  BCP; AC158 after 2<sup>nd</sup> HPR has FE

ember 5-8, 2011, Beijing, China


by W. Singer (DESY)

3 Large Grain Cavities:  
Eacc,max > 40 MV/m, after EP



# 高加速電界性能の現状@DESY

## Operational Gradient in FLASH Module ; total 56 cavities



by D. Kostin (DESY)




# 高加速電界性能の現状@FNAL

## Americas 9-cell Cavities

(Vertical Test Results)

Last test






# 高加速電界性能の現状@FNAL

## Americas 9-cell Cavities

(Horizontal Test Results for CM-2)


by A. Hocker (FNAL)

Eacc,max in VT > 30~35 MV/m



31.5 MV/m

## Cavity Gradient in CM-1@ FNAL



31.5 MV/m

by E. Harms (FNAL)

Eacc,max in VT = ave. 30 MV/m @ DESY


Eacc,max in HT = ave. 29 MV/m @ DESY  
( 3 % down)

Eacc,max in CMT = ave. 24 MV/m @ FNAL  
( 20% down)

Operational Gradient of 8 cavities < 22 MV/m ??




# 高加速電界性能の現状@ S1-G/KEK







# 高加速電界性能の現状@KEK



(Vertical Test Results for STF-2)





1. 詳細基準事前評価  
申請書

2. 高压ガス設備試験  
申請書

3. 高压ガス設備試験  
成績書

4. 高压ガス設備試験  
成績証明書 (合格証)



**Nb Cavity**  
at 1.5 times of design pressure  
(test with water : 0.3 MPa)



Inspection by  
a KHK staff



Vertical test of 9-cell cavity

**Cavity unit with Jacket**  
at 1.25 times of design pressure  
(test with He gas : 0.25 MPa)




Inspection by  
a KHK staff




Cavity string assembly




Capture Cryomodule  
(two 9-cell cavities)  
2012', Feb. Cool-down



STF-2 #1 Cryomodule  
(eight 9-cell cavities)  
2014', Jan. Cool-down





## 1. Capture Cryomodule (2)





2012', Feb. Cool-down  
(for Quantum-Beam Experiments)

## 2. Capture Cryomodule (2) + STF-2 #1 Cryomodule (8)



2014', Jan. Cool-down  
(#1; for long cryomodule performance)



## 3-a. Capture Cryomodule (2) + STF-2 #1 Cryomodule (8) + STF-2 #2 Cryomodule (4) + #3 Cryomodule (4)



Under Discussion !!

(2015', Jan. Cool-down)

## 3-b. Capture Cryomodule (2) + STF-2 #2 Cryomodule (4) + #3 Cryomodule (4)



(#2 ; for cost reduction)  
(#3 ; for R & D)

MHI-A 9-cell cavity (LBW)




MHI-B 2-cell cavity (seamless dumbbell)



by K. Sennyu (MHI)

500 MHz cavity (KEKB-Type)



Quench at 28.7 MV/m




by new EBW

- MHI-B 1 set
- 500 MHz cavity 3 sets


Under adjustment of EBW parameters for ILC/STF cavity.

**HITACHI**  
Inspire the Next

Completed HIT-01 cavity  
(no HOM couplers)



Q-E curve



**HITACHI**  
Inspire the Next

by T. Watanuki  
(Hitachi)

Current status of HIT-02 cavity with HOM couplers

(1<sup>st</sup> VT in Apr. 2012')

Completed center cells



HOM coupler



## First 9-cell cavity fabrication (TOS-01 cavity)



(no HOM couplers)

## Second 9-cell cavity fabrication (TOS-02 cavity)




(no HOM couplers)

**TOSHIBA**  
Leading Innovation >>>

by T. Ohta  
(Toshiba)


## Process optimization



Vertical test results  
(First 9-cell cavity)



Electro polish (100μm removal)



Field distribution after Pre-tuning


Now, in preparation of vertical test.

(1<sup>st</sup> VT in Jan. 2012')


EB Welding of center-cells at job-shop



Dumb-bell (Nb)




Electron Beam



EBW of end-group at CFF/KEK

Electron Beam



EBW of multiple dumbbells

by T. Saeki (KEK)



EBW failure (a hole at end-cell)



EBW assembly of center-cells at Job-shop.  
EBW assembly of end-groups at CFF/KEK.



Training for repairing a hole.



End-group

Fabrication of KEK-00 cavity  
(1<sup>st</sup> VT in Mar. 2012')

- ◆ 高加速電界の達成率は着実に向上しているが、現実的な到達値としては  $>80\%$  @  $E_{acc} > 30\text{MV/m}$  が妥当と思われる。ある確率で製作される  $20\text{MV/m}$  以下で制限される空洞への対応が必要。
- ◆ クライオモジュールでの運転加速電界の低下の原因理解については、今後数十台規模のクライオモジュールの建設 & 試験、長期間が必要。現存する8空洞内蔵クライオモジュールは、DESY(8), FNAL(2), KEK(0)。
- ◆ クライオモジュールでのビーム加速試験のためには、超伝導空洞の高圧ガス対応が必須であり、空洞開発には段階的な長期戦略が必要。

# Acknowledgements

## Special thanks go to

H. Umezawa (Tokyo-Denkai),  
K. Sennyu, H. Hitomi and H. Hara (MHI),  
T. Ohta, Y. Tajima and T. Tosaka (Toshiba),  
T. Senba, M. Watanabe and T. Watanuki (Hitachi),  
H. Hayano, S. Noguchi, T. Saeki, M. Satoh,  
T. Shishido, K. Watanabe, Y. Yamamoto (KEK)